

A Practical Guide for Commissioning Existing Buildings

Tudi Haasl
*Portland Energy Conservation, Inc.
Portland, Oregon*

Terry Sharp
*Oak Ridge National Laboratory
Oak Ridge, Tennessee*

April 1999

Prepared by
Portland Energy Conservation, Inc.
and
Oak Ridge National Laboratory
for the
Office of Building Technology,
State and Community Programs
U.S. Department of Energy
under contract DE-AC05-96OR22464

Contents

LIST OF FIGURES AND TABLES	vii
ACRONYMS AND ABBREVIATIONS	ix
ACKNOWLEDGMENTS	xi
1 INTRODUCTION	1
2 COMMISSIONING TERMINOLOGY	5
Building Commissioning	5
Existing-Building Commissioning, or Retrocommissioning	5
Continuous Commissioning	7
Recommissioning	7
Commissioning Service Providers	8
3 BENEFITS AND COSTS OF COMMISSIONING EXISTING BUILDINGS	9
4 PREPARING FOR A RETROCOMMISSIONING PROJECT	17
Is Retrocommissioning Appropriate?	17
Is an ESPC Being Considered?	18
What Resources Are Available?	19
Who Needs to Be Convinced?	20
Obtaining upper management support	20
Obtaining building operating staff support	21
5 GETTING STARTED	23
Selecting the Right Project	23
Energy management control systems	24
Absence of major system problems	24
In-house O&M staff	25
Accessible and up-to-date building documentation	25
Newer equipment	25
Cooperative building tenants	25
Energy Accounting	26
Increasing Cost-Effectiveness	28
Gather building documentation	29
Perform appropriate preventive maintenance	30
Perform simple repairs and improvements as the project progresses	30
Perform diagnostic monitoring and functional tests	31
Implement selected improvements and repairs	31

6	ROLES AND RESPONSIBILITIES OF PROJECT TEAM MEMBERS	33
	Building Owner or Owner’s Representative	34
	Commissioning Provider	34
	Typical retrocommissioning responsibilities	34
	Typical retrofit project responsibilities	35
	Additional responsibilities for consideration	36
	Building Operators	37
	Design Professionals	37
	Contractors and Manufacturer Representatives	37
	Testing Specialists	38
	Utility or Government Representative	39
7	RETROCOMMISSIONING IN ACTION	41
	Planning Phase	41
	Developing and communicating the objectives	41
	Choosing the team and hiring the commissioning provider	46
	Reviewing and updating building documentation	49
	Developing the plan and holding a scoping meeting	50
	Planning phase deliverables	51
	Investigation Phase	51
	Performing a site assessment	52
	Developing the Master List of deficiencies and potential improvements	53
	Developing the diagnostic monitoring and test plans	54
	Implementing the diagnostic monitoring and test plans	56
	Selecting the most cost-effective opportunities for implementation	57
	Investigation phase deliverables	58
	Implementation Phase	58
	Implementing improvements	58
	Retesting and remonitoring	59
	Implementation phase deliverables	60
	Project Hand-Off Phase	60
	Completing the final report	60
	Maintaining the investment benefits	61
	Project closeout meeting	63
	Hand-off phase deliverables	63
8	ORGANIZATION-WIDE PLANNING	65
9	CONCLUSION	67
10	BIBLIOGRAPHY	69
APPENDICES		
A	Sources for Commissioning Guidelines, Guide Specifications, and Sample Functional Performance Tests	A-1
B	Building Information Summary	B-1

C	Checklist of Building Documentation	C-1
D	Commissioning Tools Checklist	D-1
E	Commissioning Firm Experience	E-1
F	Request for Proposal Checklist for Retrocommissioning Services	F-1
G	Sample Retrocommissioning Plan	G-1
H	Sample Site Assessment Forms	H-1
I	Sample Master List	I-1
J	Sample Diagnostic Monitoring and Trending Plans	J-1
K	Sample Functional Performance Tests	K-1

Figures and Tables

Figures

1	The phases and activities of the retrocommissioning process	42
2	Example of prioritized, written objectives for a commissioning project	44
3	Example of data analysis using data derived from a portable data logger	55
4	Example of a list of recommended capital improvements	61

Tables

1	The four phases of the retrocommissioning process	3
2	New-construction commissioning vs retrocommissioning	6
3	Benefits of commissioning existing buildings	9
4	Summary of recent cost and savings for recently commissioned existing buildings	10
5	Cost of losing a tenant	16
6	Characteristics that improve retrocommissioning value	23
7	Distribution of annual total energy use intensities (EUIs) for commercial buildings	27
8	Summary of retrocommissioning activities and products	43

Abbreviations and Acronyms

A/C	air conditioner
DOE	U.S. Department of Energy
EMCS	energy management control system
EPA	U.S. Environmental Protection Agency
ESPC	energy savings performance contract
EUI	energy use index
HVAC	heating, ventilating and air-conditioning
IAQ	indoor air quality
M&V	measurement and verification
O&M	operation and maintenance
ORNL	Oak Ridge National Laboratory
OSA	outside air
OSHA	Occupational Safety and Health Administration
PM	preventive maintenance
RFP	request for proposal
RFQ	request for qualifications
ROI	return on investment
TAB	testing, adjusting and balancing
TN	total number
TOD	time of day
VAV	variable-air-volume
VFD	variable frequency drive

Acknowledgments

The authors would like to express their appreciation to Peter Herzog of Herzog/Wheeler and Associates and to Bil Pletz for their thorough reviews and insightful comments that helped improve this guide.